Abstract for constructing a 3rd class travellers' bungalow at Hosdurga (with steel roof):—

| No. | Items of work. | Per | Quantity. |
|---|---|---|---|
| 1 | Earthwork, excavation ... ... ... | C. yd. | 217 |
| 2 | Burnt stone in chunam ... ... ... | C. ft. | 6,159 |
| 3 | Burnt brick in chunam ... ... ... | ,, | 5098 |
| 4 | Burnt brick in chunam (arch work) ... ... | ,, | 50 |
| 5 | Burnt stone slabs ... ... ... | S. ft. | 683 |
| 6 | Plastering with chunam ... ... | Sqr. | 38·20 |
| 7 | Do do rough ... ... | ,, | 41·72 |
| 8 | Pointing with chunam ... ... ... | Sqr. | 5·15 |
| 9 | White and color washing ... ... ... | ,, | 85·07 |
| 10 | Flooring with Mangalore tiles over 3" concrete, etc. ... | ,, | 6·02 |
| 11 | Flooring with Cuddapah slabs do ... | ,, | 5·03 |
| 12 | Roofing with 1st class Mangalore tiles excluding teak reepers | ,, | 34·43 |
| 13 | Ridge tiles set in mortar ... ... ... | Rft. | 159 |
| 14 | Ventilating tiles ... ... ... | Each | 12 |
| 15 | Steel works ... ... ... ... | Cwt. | 92½ |
| 16 | Teakwood doors pannelled ... ... | S. ft. | 224 |
| 17 | Do windows outside pannelled inside glazed with iron bars, etc., complete ... ... | S. ft. | 70 |
| 18 | Teakwood battened doors ... ... ... | S. ft. | 111 |
| 19 | Do do windows, outside battened shutters, inside glazed shutters with iron bars ... | ,, | 9 |
| 20 | Teakwood battened windows with iron bars ... | ,, | 8 |
| 21 | Do do ventilators glazed ... | ,, | 4 |
| 22 | Cut stone pillars with capitals, etc. ... ... | Each | 6 |
| 23 | Ornamental eave-board, 9" depth, 1" thick ... | Rft. | 161 |
| 24 | Painting doors and windows and eave-boards ... | Sqr. | 12·69 |
| 25 | Clearing site, levelling ground and fencing ... | L. S. | .. |
| 26 | Flooring with gravel ... ... | Sqr. | 4·89 |
| 27 | Cornice work at gable ends ... ... | Rft. | 76 |
| 28 | Stone flagging with cement pointing ... ... | Sqr. | 1·20 |
| 29 | Sinking a new well ... ... ... | L. S. | |
| 30 | Constructing a latrine ... ... ... | ,, | ... |

K. PRAHLADA RAO,
*Exec. Engineer.*

## WATER-SUPPLY AND STORES DIVISION.

*Dated 1st November* 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Water-supply and Stores Division, up to 23rd November 1906, for lining with surki concrete and cement-plastering the settling tanks at Vantikoppal, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for concrete-lining and cement-plastering tanks at Vantikoppal," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of quantities for lining with surki concrete and cement-plastering the settling tanks at Vantikoppal, Mysore :—

| Items of work | Per | Quantity |
|---|---|---|
| Removing the edge stones ... ... ... | S. ft. | 2,386 |
| Refixing the edge stones ... ... ... | S. ft. | 2,386 |
| Easing slopes with required pitting and filling ... | C. yd. | 1,393 |
| Filling concrete for slopes ... ... ... | C. ft. | 37,607 |
| Removing old plastering surki ... ... | Sqr. | 608·00 |
| Plastering with ½" thick cement ... ... | ,, | 973·75 |
| Sundry repairs, etc. ... ... ... | Item | L. S. |
| Cement pointing ... ... ... ... | S.qr. | 31·82 |
| Cleaning all round the tank after completion of work... | Item | L. S. |
| Clearing silt from beds of tanks ... ... | Item | L. S. |

K. SRINIVAS IYENGAR,
for *Executive Engineer.*

## BANGALORE CITY MUNICIPALITY.

*Notice dated 2nd November* 1906.

It is hereby notified for the information of the public that the Grain Bazaar zinc sheds situated in the triangular plot of ground between the north-west diagonal road and the north road at the north-west corner of the Basavangudi Extension will be sold by public auction on the spot by the undersigned at 8 A. M. on Tuesday the 4th proximo.

2. The purchaser should deposit at the time of sale twenty-five per cent of the purchase money and pay the remainder within fifteen days from the date of sale, failing which, the property will be re-sold at the risk of the first purchaser.

3. The undersigned reserves the power of accepting or refusing the highest or any bid.

4. The purchaser should pull down the sheds and remove the materials within a period of fifteen days from the date of confirmation of the sale, failing which, they will be re-sold at the risk of the purchaser.

5. The sale is subject to confirmation by the President.

M. G. KRISHNASAMI RAO,
for *President.*

*Notice dated 8th November* 1906.

It is hereby notified for the information of the public that the marginally noted sites in the Basavangudi and Mallesvaram Extensions, Bangalore City, will be sold by public auction on the spot at 8 A.M., on the 7th and 8th December 1906, respectively.

| Block No. | (1) Basavangudi Extension. | | Date of sale | (2) Mallesvaram Extension. | | Date of sale |
|---|---|---|---|---|---|---|
| I | Shop sites 165 and 169 | 120×30 | 7-12-1906. | Sampige road 526 | 120×21 | 8-12-1906. |
| III (*a*) | house site 198 | 110×30 | | Do 523, 524, 525 | 120×30 | |
| III (*b*) | Do 20 | 117×30 | | Hindu block 100 | 100×30 | |

2. The purchaser should deposit at the time of sale twenty-five per cent of the purchase money and pay the remainder within fifteen days from the date of sale, failing which the land will be re-sold at the risk of the purchaser.

3. The President reserves the power of accepting or refusing the highest or any bid.

4. As to the other conditions of sale, the public are referred to the detailed notice issued in this connection in the Kanarese portion of the Gazette.

5. The sale is subject to confirmation by the President.

H. H. SPARKES,
*President.*